

North—south component of horizontal ground acceleration recorded at the Imperial Valley Irrigation District substation, El Centro, California, during the Imperial Valley earthquake of May 18, 1940.

Program:

Step1: verify

The time variation of the deformation induced by this ground motion for SDF systems (natural Period=0.5,damping=0.02)

```
% NAME of PROGRAM : The time variation of the deformation induced by
%this ground motion for SDF systems (natural Period=0.5,damping=0.02)
% WRITER BY: ALI SALEHI (Pcc.s@hotmail.com)
% Start Program
clc
clear
close all
% DELTA t:Dt
Dt=0.02; %sec
q=386; %in/sec2
nr=195;
nc=8;
%Input data ground acceleration record
acc=zeros(1,nr*nc);
z=importdata ('H:\ELCENTRO2.DAT');
m=1;
for jr=1:nr;
for jc=1:nc;
acc(m) = z(jr, jc);
m=m+1;
end
end
%KESI: D
D=0.02;
```

Ali Salehi